BROWN, ERDMAN & TURNER LTD.

1409 BEWICKE AVENUE, NORTH VANCOUVER, BRITISH COLUMBIA V7M 3C7 TELEPHONE 988-1557

> Domestic Wall No3 T.W. No6

GROUNDWATER DEVELOPMENT HATCH POINT, B.C. FOR

CRC CANADIAN RETIREMENT CORPORATION AND

APLIN & MARTIN ENGINEERING LTD.

HATCH POINT DOMESTIC WELL NO. 3

Ву

W.L. Brown, P. Eng.

August, 1988



1.0 INTRODUCTION

- 1.1 Location Hatch Point Domestic Well No. 3 is located 60 m west of Ratcliff Road and 180 m north of Hutchinson Road. Please see well location map, Fig. 1.
- 1.2 Drilling and Testing The construction of Domestic Well No. 3 started on June 30 and finished on July 19, 1988. A constant rate pump test was conducted on August 10 and 11, 1988.

2.0 HYDROGEOLOGY (Please see Isometric Diagram, Fig. 2 attached)

- 2.1 Bedrock Domestic Well No. 3 was drilled to granitic bedrock at a depth of 53.95 m. Granitic bedrock was also encountered in Domestic Wells No. 1 and 2 and sandstone was encountered in Irrigation Well No. 1. Thus the fault that forms the contact between the granitic and sandstone rocks trends in a northwesterly direction which is most probably coincident with the topographic grain of the country.
- 2.2 Unconsolidated Sediments Sands and sand and gravel with one thin silt bed were drilled to a depth of 43.28 metres where a clay was encountered.

3.0 WELL CONSTRUCTION

Domestic Well No. 3 was drilled by a cable tool rig.

Reference to the well log attached will show that the well is cased with 305 mm diameter casing to a depth of 37.80 m. A screen assembly consisting of a 178 mm diameter riser 1.52 m long, a 4.57 m length of stainless steel, 10 slot, 203 telescopic diameter well screen and a 3.05 m long, 178 mm diameter sump is set between depths of 37.19 and 46.33 m. The screen was developed by bailing.

4.0 PUMP TESTING

A constant rate pump test was conducted on Domestic Well No. 3 during August 10/12, 1988 at a discharge rate of 164 m³/day (25 I gpm). Drawdown water level readings were taken and recorded during a 2,900 minute (slightly over two day) period of pumping and recovery water level measurements were recorded for 60 minutes after pumping stopped. The water levels in Irrigation Wells No. 1 and No. 2 were measured and recorded during the pumping of Domestic Well



No. 3. Reference to the pump test data well shows that the water levels in these two wells rose 2.830 and 0.175 metres respectively during the test. Unfortunately, these two wells could only be shut-off just before the test started. However, these readings indicate that interference between and these irrigation wells Domestic Well No. 3 Fig. 2 will show that Reference to insignificant. interference between Irrigation Well No. 1 and Domestic Well No. 3 would not be expected. Minor interference between Domestic Well No. 3 and Irrigation Well No. 2 could be expected.

Please see the details of the pump test, the log of the well and the semi-log plots of the drawdown and recovery readings. The transmissivity of the last leg of the drawdown plot at 53 m²/day (4,200 U.S. gpd/ft) is considered realistic. This figure is lower than the 76 to 100 m²/day (6,000 to 8,000 U.S. gpd/ft) transmissivity figures calculated from the pump tests run on Domestic Wells No. 1 and No. 2.

The water level in Domestic Well No. 3 reached near stabilization at a depth of 32.70 meters between 900 and 1,300 minutes of pumping. This is 6.01 metres above the top of the well screen at a depth of 38.71 metres. The discharge rate fluctuated and was increased at 1400 minutes. This increase with a probable interference from a neighbouring well caused a water level drop of approximately 0.458 m. The well was again trending towards stabilization when the pump test was stopped.

Based upon available information we judge that Domestic Well No. 3 has a safe productive capacity of 260 \rm{m}^3/\rm{day} (40 I gpm).

The production pump should be "shrouded" and set in the sump below the screen to allow the water level to be drawndown to the top of the screen. The pump should be capable of discharging at a rate of $260~\text{m}^3/\text{day}$ (40 I gpm) from a water level depth of 38 m with the pump suction at a depth of 44 m. The total dynamic head of the pump should be 38 m plus the system pressure.

5.0 WATER QUALITY

A sample of water was collected prior to the end of the pump test and was sent to a commercial laboratory for



chemical analysis. Please see chemist's report attached. This water should have been similar to the waters from the other wells.

Reference to the chemist's reports will show the following:

Domestic Well	Total (mg/l)		Dissolved (mg/l)		
Number	Iron	Manganese	Iron	Manganese	
1	0.30	0.05	less than 0	.03 0.050	
2	0.30	0.05	less than 0	.03 0.011	
3	1.63	0.23	less than 0	.03 0.210	

The chemist's report on the water from Domestic Well No. 3 indicates that the iron is contained in the suspended solids which have a concentration of 2.0 mg/l. The filtered sample has a concentration of dissolved iron of less than 0.03. Further pumping which should decrease the suspended solid concentration should also decrease the total iron content to less than 0.30. The chemist's report notes that the limits for iron and manganese are set in the drinking water guidelines for aesthetic reasons and not physiological reasons.

6.0 RECOMMENDATIONS AND CONCLUSIONS

- 6.1 Based upon presently available information the safe productive capacity of Domestic Well No. 3 is 260 m³/day (40 I gpm).
- 6.2 This well should NOT be

overpumped vibrated raw-hided

- 6.3 The new concrete cribbings that will be constructed around Domestic Well No. 3 will change the datum of the measuring point from that used on the well logs and pump tests attached to this report. The relationship between the original ground surface and the new top of cribbings should be established and recorded.
- 6.7 Water level measurements should be made and recorded in all wells during the first five years of operation. These records should be reviewed by the writer once a year.

CHEMICAL ANALYSIS REPORT



Date:

August 26, 1988

File No.

6120A

Report On:

Water Sample From Arbutus Ridge

Report To:

Brown Erdman & Turner Ltd.

1409 Bewicke Avenue North Vancouver, B. C.

V7M 2W0

DATE OF SUBMISSION:

August 16, 1988

SAMPLE IDENTIFICATION

Labelled as shown in RESULTS section.

METHODOLOGY

Analysed in accordance with "Standard Methods for the Examination of Water and Wastewater" published by the American Public Health Association, 1985.

RESULTS OF ANALYSIS

Results are presented in the table(s) attached.



analytical service laboratories ltd.

CONSULTING CHEMISTS & ANALYSTS
1650 Pandora Street
Vancouver, B.C. • V5L 1L6
Fax (604) 253-6700 • Tel. (604) 253-4188

REMARKS

File No. 6120A Page 2 of 3

The water as represented by the sample submitted can be characterized as moderate with respect to dissolved mineralization.

The water sample met drinking water guidelines for all parameters analysed with the exception of iron and manganese. These parameter are limited for aesthetic purposes (i.e., appearance, taste, etc.) rather than health considerations. Their presence would likely cause a "metallic" taste.

ASL ANALYTICAL SERVICE LABORATORIES LTD.

A. W. Maynard, M.Sc.

Senior Partner

Barbara Szczachor, B.Sc.

BS/AWM/mm



RESULTS OF ANALYSIS

File No. 6120A Page 3 of 3

		Arbutus Ridge	Drinking*1 Water Guidelines
Physical Te	sts		
pH Conductivit Colour Turbidity Suspended S Dissolved S Hardness	NTU olids	7.51 46. 5. 3.7 2.0 124 78.6	6.5-8.5
Anions and	Nutrient	<u>:s</u>	
Alkalinity Sulphate Chloride Fluoride NO3/NO2	CaCO3 SO4 Cl F N	87.0 <1.0 3.6 0.11 0.022	500. 250. 1.5
Total Metal	<u>.8</u>		
Iron Manganese	T Fe T Mn	1.63 0.23	0.30 0.05
Dissolved M	letals		
Arsenic Barium Cadmium Chromium Copper	D As D Ba D Cd D Cr D Cu	0.0022 <0.010 <0.0002 <0.015 <0.010	0.05 1.0 0.005 0.05 1.0
Iron Lead Manganese Zinc	D Fe D Pb D Mn D Zn	<0.03 <0.00005 0.21 0.010	0.05 5.0
Calcium Magnesium Potassium Sodium	D Ca D Mg D K D Na	17.8 8.12 0.83 6.16	- - - *3

< = Less than
Results expressed as milligrams per litre except for pH,
Conductivity (µmhos/cm), Colour (CU), Turbidity (NTU)
*1 "Maximum acceptable concentration" as published by Health & Welfare Canada,
1985</pre>

^{*2} Maximum level not established - water supplies with a hardness exceeding 200 mg/L are considered poor but will be tolerated. Not a health consideration #3 Maximum level not established - of concern to consumers with sodium restricted diet. Levels exceeding 20 mg/L may be of concern in this circumstance.

HATCH POINT

DOMESTIC WELL NO. 3

Depth (Below Ground	Surface)	Description
Metres	Feet	
0.00 - 1.52 1.52 - 24.69 24.69 - 26.52 26.52 - 28.00 28.04 - 30.48 30.48 - 43.28	$ \begin{array}{rrrr} 0 & - & 5 \\ 5 & - & 81 \\ 81 & - & 87 \\ 87 & - & 92 \\ 92 & - & 100 \\ 100 & - & 142 \end{array} $	Sandy, loam Sand and gravel, silty Silt, tight Sand, with pebbles, silty Sand and gravel, silty Sand, fine to medium
43.28 - 48.77 48.77 - 53.95 53.95 -	142 - 161 161 - 177 177 -	<pre>grained water-bearing Clay, silty Clay with cobbles (till-like) Bedrock, granite</pre>

Construction Details - below ground surface

	Metres	
305 mm (12-inch) diameter casing 178 mm (7-inch) diameter riser 203 mm (8-inch) telescopic diameter screens	00.00 - 37.80 37.19 - 38.71 38.71 - 43.28	00.00 - 124 122 - 127 127 - 142
178 mm (7-inch) diameter sump	43.28 - 46.33	142 - 152

Screens - stainless steel, 10 slot

CONSTANT RATE PUMP TEST

DRAWDOWN

Date: August 10/12, 1988

Discharge Rate: 30 U.S. gpm, 25 I gpm or $164 \text{ m}^3/\text{day}$

Time of Day	Elapsed Time	Depth to	Drawdown	Comments
02 247	Minutes		Metres	
Aug. 10	0.0	24.857	0.000	Measuring Point-top of casing 0.56 m above existing ground
1100	0.5	25.780	0.923	Discharge - 152 m from well
	1.0	27.180	2.323	Flow rate checked by watch
	1.5	29.000	4.143	and container
	2.0	29.777	4.920	
	2.5	30.465	5.608	
	3.0	30.122	5.265	42 US gpm or 234 m ³ /day
	3.5	30.614	5.757	
	4.0	31.071	6.214	Decreasing discharge
	4.5	31.852	6.995	
	5.0	32.635	7.778	
	6.0	33.182	8.325	
	7.0	33.609	8.752	
	8.0	33.969	9.112	
	9.0	34.200	9.343	
	10	34.381	9.524	
	12	34.466	9.609	
	14	34.433	9.576	
	16	34.309	9.452	
	18	34.221	9.364	30 US gpm or 164m ³ /day
	20 25	34.221	9.364	120 09 dbu or 10411 / day
	30	34.179	9.322	-
	35	33.628	8.771	
	40	33.020	8.321	
	45	33.002	8.145	29.7 US gpm or 162 m ³ /day

CONSTANT RATE PUMP TEST

DRAWDOWN

Time		Depth to	Drawdown	Comments
of Day	Time Minutes	Water Metres	Metres	
			- 055	
	50	32.732	7.875	29.7 US gpm or 162m ³ /day
1200	60	32.632	7.775 7.776	29.7 05 gpm of 102m 7 day
	70 80	32.633 32.552	7.695	29.7 US gpm or 162m ³ /day
	90	32.532	7.675	
	100	32.533	7.676	29.7 US gpm or 162m ³ /day
	125	32.544	7.687	22
	150	32.554	7.697	
1420	200	32.560	7.703	
, 420	250	32.574	7.717	
	300	32.580	7.723	
	350	32.596	7.739	
	400	32.600	7.743	
	450	32.608	7.751	460-3/4
	500	32.617	7.760	29.7 US gpm or 162m ³ /day
	550	32.620	7.763	
	600	32.631	7.774	
	650	32.647	7.790	
	700	32.665	7.808	
	750	32.675	7.818	
Aug. 11		32.685	7.828	
0110	850	32.695	7.843	
	900	32.700	7.843	
	1000	32.700	7.838	29.7 US gpm or 162m ³ /day
	1050	32.695	7.838	Jr. 32 Jr.
	1100	32.700	7.843	
•	1150	32.705	7.848	
0700	1200	32.700	7.843	
0700	1250	32.710	7.853	
	1300	32.700	7.843	2
	1350	32.685	7.828	28 US gpm or 153m ³ /day
	1400	32.658	7.801	
	1450	33.158	8.301	30 US gpm or 164m ³ /day
	1500	33.158	8.301	
1250	1550	33.158	8.301	2.13
	1600	33.159	8.302	30 US gpm or 164m ³ /day
	1650	33.160	8.303	

CONSTANT RATE PUMP TEST

DRAWDOWN

Time		Depth to	Drawdown	Comments
of Day	Time	Water		
	Minutes	Metres	Metres	
	1700	33.164	8.307	30 US gpm or 164m ³ /day
	1750	33.164	8.307	3 /-
	1800	33.166	8.309	30 US gpm or 164m ³ /day
	1850	33.167	8.310	3.4
	1900	33.175	8.318	30 US gpm or 164m ³ /day
	1950	33.179	8.322	2.5
2020	2000	33.181	8.324	30 US gpm or 164m ³ /day
	2050	33.189	8.332	3.5
	2100	33.209	8.352	30 US gpm or 164m ³ /day
	2150	33.220	8.363	1
Aug 12	2200	33.225	8.368	2 /-
0030	2250	33.235	8.378	30 US gpm or 164m ³ /day
	2300	33.245	8.388	1
	2350	33.250	8.393	
0300	2400	33.260	8.403	2
	2450	33.265	8.408	30 US gpm or 164m ³ /day
	2500	33.270	8.413	3 (2
	2550	33.280	8.423	30 US gpm or 164m ³ /day
	2600	33.280	8.423	
4	2650	33.280	8.423	
0800	2700	33.275	8.418	
	2750	33.285	8.428	2.5
	2800	33.285	8.423	30 US gpm or 164m ³ /day
	2850	33.285	8.428	
1120	2900	33.280	8.423	Water Sample Collected
1200	2940	33.280	8.423	Pump off

CONSTANT RATE PUMP TEST

RECOVERY

Time	Elapsed	Depth to	Drawdown	Time Since Pumping Started Divided by Time
of Day	Time	Water Metres	Metres	Since Pumping Stopped
	Minutes	Metres	Metres	Billed Tamping Bookle
Aug 12				
1200	0.0	33.280	8.423	
. 200	0.5	32.334	7.477	5881
	1.0	31.745	6.888	2941
	1.5	31.071	6.214	1961
	2.0	30.537	5.680	1471
	2.5	30.029	5.172	1177
	3.0	29.582	4.725	981
	3.5	28.170	3.313	841
	4.0	27.825	2.968	736
	4.5	27.481	2.624	654
	5.0	27.189	2.332	589
	6.0	26.710	1.853	491
	7.0	26.330	1.473	421
	8.0	26.020	1.163	368
	9.0	25.770	0.913	328
	10	25.584	0.727	295
	12	25.300	0.443	246
	14	25.129	0.272	211
	. 16	25.029	0.172	185
	18	24.956	0.099	164
	20	24.910	0.053	148
	25	24.861	0.004	119
	30	24.844	-0.013	99
	35	24.831	-0.026	85
	40	24.829	-0.028	75
	45	24.824	-0.033	66
	50	24.823	-0.034	60
1300	60	24.820	-0.037	50

HATCH POINT DOMESTIC WELL NO. 3 CONSTANT RATE PUMP TEST

IRRIGATION WELLS NO. 1 & 2 USED AS OBSERVATION WELLS DRAWDOWN

Date: August 10/12, 1988

Time	Elapsed	Depth to Water M	Depth to Water M
of Day	Time	7.	T 17-11 27- 0
	Minutes	Irr Well No. 1	Irr Well No. 2
Aug 10/88			
1100	0.0	Shut-off	Shut-off
1210	70	36.735	27.435
1305	125	36.410	27.420
	150	35.852	27.370
	200	35.578	27.231
	250	35.334	27.321
1650	350	35.057	27.310
	550	34.600	27.310
	750	34.155	27.285
Aug 11/88	950	34.500	27.285
0610	1150	34.000	27.275
	1400	34.010	27.275
	1600	34.010	27.275
	1850	34.010	27.270
	2050	34.010	27.270
	2250	34.010	27.265
	2450	34.015	27.265
	2650	33.905	27.260
	2940	}	Shut down test

DRAWDOWN

METRES

46 6212